

15-735-2048 7-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 4 1971  
CONSERVATION DIVISION  
Wichita, Kansas  
10-4-71

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Operator's Full Name Murfin Drilling Company

Complete Address 617 Union Center Wichita, Kansas

Lease Name Schliffke Well No. 1

Location 150' SW of C NW SW Sec. 26 Twp. 20 Rge. (E) (W) 25

County Ness Total Depth 4490

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Co. Tools

Address        License No.       

Operation Completed: Hour 4 A Day 27 Month 9 Year 1971

The above well was plugged as follows:

RTD 4490' 8 5/8 csg set at 570' cwc Cmt. Mat. 50-50 poz W/4% added gel.

Gunned pits, circulated heavy mud, set cementing plug at 720' and displaced 50 sk

cmt thru drill pipe. Heavy mud to 400' set cementing plug and displaced 25 sk cmt

thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to

base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 10/5/71  
INV. NO. 4426-11

Signed: Red J. Massey  
Well Plugging Supervisor