

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
P. O. Box 17027  
Wichita, Kansas 67217

RECEIVED  
STATE CORPORATION COMMISSION  
APR 17 1974  
4-17-74  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Twin Western Resources, Inc.

Complete Address 200 E. 1st. Suite 518, Wichita, Kansas

Lease Name Copeland Well No. 1

Location NW NE Sec. 24 Twp. 20 Rge. (E) (W) 25

County Ness Total Depth 4462

Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XX

Other well as hereafter indicated       

Plugging Contractor Abercrombie Drlg.

Address Wichita, Kansas License No.       

Operation Completed: Hour 7 P Day 15 Month 4 Year 1974

The above well was plugged as follows:

RTD 4462' 8 5/8 csg set at 407' cwc Cem. Mat. 50-50 poz 6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 650' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 300' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Reg J. Massey  
Well Plugging Supervisor

DATE 4/17/74

INV. NO. 8942-W