

15-135-19038-0000
Form CP-3
Rev. 6-26-62

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUL 9 1963
7-9-63
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Ferguson Oil Co
Complete Address: 522 Union Center Wichita, Kansas
Lease Name Copeland Well No. X 4
Location CNE SW Sec. 24 Twp. 20 Rge. (E) (W) 25
County Ness Total Depth 4496
Abandoned Oil Well X Gas Well Input Well SWD Well D & A
Other well as hereafter indicated:
Plugging Contractor: Glenn & Smith
Address: Ellinwood, Kans License No. 396
Operation Completed: Hour 10:30AM Day 7 Month 7 Year 63

The Above well was plugged as follows:

8 5/8 519' circulated with cement - 5 1/2" 4495' with 100 sax cement -
PB to 4459' - perforated 4438'

Filled with sand to 4420', set 4 sax cement with dump bailer - pulled
3000' 5 1/2" - filled hole with heavy chunk mud to 520', set 20 sax cement
at 520' - heavy chunk mud to 200', set 20 sax cement at 200', heavy chunk
mud to 35', cement 35' to 0'

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 7/9/63

INV. NO. 7287-W

Signed: Edson Kelly
Well Plugging Supervisor