

15-65-20228-0000

Form CP-3
Rev. 6-26-62

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
4-3-69
APR 3 1969
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Operator's Full Name Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kansas

Lease Name Behner "B" Well No. 1

Location NW NW SE Sec. 30 Twp. 19 Rge. 20 (E) (W) XX

County Rush Total Depth 4425'

Abandoned Oil Well Gas Well Input Well SWD Well D & A XX

Other well as hereafter indicated:

Plugging Contractor: Go. Tools

Address: License No.

Operation Completed: Hour 10P Day 31 Month 3 Year 1969

The Above well was plugged as follows:

RTD 4425' 8 5/8 csg set at 250' cwc 185 sk. Gmt Mat. 50-50 poz cmt W/6% total gel.

Gunned pits, circulated heavy mud, set cementing plug at 600' and displaced 70 sk cmt
thru drill pipe. Heavy mud to 240' set cementing plug and displaced 20 sk cmt thru
drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to base
of cellar. Plugged rat hole with 2 sk cmt.

I hereby certify that the above well was plugged as herein stated.

Signed: Bro J. Massey
Well Plugging Supervisor

INVOICED
DATE 4/3/69
INV. NO. 9545-a