

15-165-20325-0000

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 23 1970  
CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Pickrell Drilling & Southwest Petro - Chem.  
Complete Address 705 4th Nat'l Bank Bldg., Wichita, Kansas  
Lease Name Westermeyer "I" Well No. 1  
Location NW NE SW Sec. 30 Twp. 19 Rge. (E) (W) 20  
County Rush Total Depth 4470  
Abandoned Oil Well        Gas Well        Input Well        SWD Well        D & A XXX  
Other well as hereafter indicated         
Plugging Contractor Pickrell Drlg.  
Address Wichita, Kansas License No.         
Operation Completed: Hour 1:30A Day 21 Month 6 Year 1970

The above well was plugged as follows:

RTD 4470' 8 5/8 csg set at 260' cwc Cmt. Mat. 100 sk reg. poz W/6% gel  
Gunned pits, circulated heavy mud, set cementing plug at 650' and displaced 70 sk  
cmt thru drill pipe. Heavy mud to 275' set cementing plug and displaced 20 sk cmt  
thru drill pipe. Heavy mud to 40' set cementing plug, 1/2 sk hulls and 10 sk cmt to  
base of cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Leo F. Massey  
Well Plugging Supervisor

DATE 6/23/70  
INV. NO. 2091-W