

R

Form CP-3  
Rev. 6-4-68

KANSAS

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

FEB 24 1977  
2-2477

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -165-20375-0000 (of this well)

Operator's Full Name Pickrell Drilling Company

Complete Address 205 Litwin Bldg., Wichita, Kansas 67202

Lease Name Dehner "C" Well No. 1

Location C SE SE Sec. 30 Twp. 19 Rge. (E) (W) 20

County Rush Total Depth 4395'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Pipe Pullers, Inc.

Address Box 486, Ellinwood, Kansas 67526 License No. 462

Operation Completed: Hour 3:30 P Day 22 Month 2 Year 1977

The above well was plugged as follows:

RTD 4395' 8 5/8 csg set 270' cwc 150 sx.

5 1/2 csg set 4390' cw 175 sx cem.

Filled 5 1/2 csg W/sd (4395'-4375') dumped 4 sk cem W/dump bailer. (4375'-4345')

Cutoff & recovered 3221' of 5 1/2 csg.

Allied Cementing Co. mixed & pumped down 8 5/8 csg with 20 sk gel & water W/100 lbs  
hulls, followed with 70 sk 50-50 poz 6% gel -displaced with 5 sk gel & water -  
released 8 5/8 plug & capped with 50 sk 50-50 poz 6% gel & shutin. MPP 350 lbs.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Leo Massey  
Well Plugging Supervisor

DATE 2-25-77

INV. NO. 4692-W