



02

15-175-00010-0000

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

MAR 21 1972

CONSERVATION DIVISION  
Wichita, Kansas

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Jewett of Venus has this

date requested permission to plug the following described well:

Mr. Jewett guarantees payment of the plugging fee.

Operator's full Name: Venus Oil Company

Complete Address: 1200 N.B.C. Bldg., San Antonio, Texas

Lease Name: Iris Well No. 1

Location: C SE SW Sec. 11 Twp. 34 Rge. 31 XX (E) (W)

County: Seward Total Depth 6030' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Jewett was instructed to plug the well as follows:

8 5/8" to 1555' circulated w/ cement. 5 1/2" to 6030' cemented.

Top perforations 3024' Plug bottom w/ 25 sacks cement.

Top of cement 2800' Mud 2800' to 1580'

Spot 35 sacks cement 1580' to 1480' Mud 1480' to 45'

Plug, Hulls & 15 sacks cement 45' to 0'.

Very truly yours,

  
Conservation Division Agent