

State of Kansas

FORM CP-2



JOHN CARLIN  
R. C. LOUX  
JANE T. ROY  
PHILLIP R. DICK  
CAROL J. LARSON

Governor  
Chairman  
Commissioner  
Commissioner  
Executive Secretary

State Corporation Commission

CONSERVATION DIVISION  
(Oil, Gas and Water)

200 Colorado Derby Building  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To be filed by Plugging Agent)

Dear Sir:

Mr. Ed Weiler of Shields Drilling Co., Inc. has this date requested permission to plug the following described well:

Operator's Full Name: V. Francis Weigel

Complete Address: Box 244, Gorham, Ks. 67640

Lease Name: Chesney "B" Well No. #5

Location: Center of E/2-SE-SE Sec. 6 Twp. 11 Rge. 16 (E) (W)

County: Ellis Total Depth: 3500'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereafter indicated:

Mr. Ed Weiler was instructed to plug the well as follows:

8 5/8"-209' sp. w/165 sacks common-2% Gel-3% Cal. Cl.

Ordered 130 sacks 50/50 posmix-4% Gel-3% Cal. Cl. and 8 5/8" plug.

Spotted with drill stem, with heavy mud between all plugs.

1st plug @ 810' w/70 sacks cement

2nd plug @ 210' w/40 sacks cement

3rd plug-solid bridge of hulls and plug @ 40' w/10 sacks cement

5 sacks of cement in rat hole and 5 sacks of cement in house hole.

Very truly yours,

[Signature]  
Conservation Division Agent  
Wichita, Kansas

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 13 1981  
10-13-81