



15-195-33072-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 31 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Adminstrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pulley of Forbes Casing Pulling Inc this

date requested permission to plug the following described well:

Western Oil Field Service.

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Glen Armour dba Western Oil Field Service,

Complete Address: Box #163, Great Bend, Kansas.

Lease Name: Kellar Well No. 2

Location: N $\frac{1}{2}$ -NE Sec. 9 Twp. 13 Rge. (E) (W) 21

County Trego Total Depth 3890 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Pulley was instructed to plug the well as follows:

208'--8 5/8" Surface pipe, cement circulated.  
3887'--4 1/2" Production casing cemented with 50 Sx. Well plugged  
back to 3885'. Top perforations @ 3878'.

Sand back to 3850' and set 5 Sx. cement with dump bailer.  
Pull 4 1/2" casing to 600' and circulate heavy gel mud. Pull 4 1/2"  
to 540' and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2" to 180'  
and displace 20 Sx. cement thru 4 1/2". Pull 4 1/2", set bridge @  
30' and 10 Sx. cement to bottom of surface.

Very truly yours,

H. L. Nichols  
Conservation Division Agent