



15-195-00259-0001

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

DEC 28 1964

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. D. B. Pulley of Forbes Csg. Pulling Inc., has this

date requested permission to plug the following described well:

Western Oil Field Service,

Mr. Pulley guarantees payment of the plugging fee.

Operator's full Name: Glen E. Armour (dba) Western Oil Field Service,

Complete Address: Box #163, Great Bend, Kansas.

Lease Name: Keller Well No. 1

Location: N/2-NE Sec. 9 Twp. 13 Rgs. (E) (W) 21

County Trego Total Depth 3959 Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Pulley was instructed to plug the well as follows:

216'--8 5/8" Surface pipe, cement circulated.

3958'--5 1/2" Production casing cemented with unknown amount of cement. Well plugged back to 3919'. Top of perforations @ 3890'. Well squeezed in the Dakotas.

Sand well back above perforations to 3875' and set 5 Sx. cement with dump bailer. Pull 5 1/2" to 600' and circulate heavy gel mud. Pull 5 1/2" to 540' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2" to 210' and displace 20 Sx. cement thru 5 1/2". Pull 5 1/2", set bridge @ 30' and 10 Sx. cement.

Very truly yours,  
M. L. Dechels  
Conservation Division Agent