



JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission
 CONSERVATION DIVISION
 (Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

MAY 16 1963
 5-16-63
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Percy Hall of Pickrell Drilling Co. has this

date requested permission to plug the following described well:

Mr. Hall guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Co.

Complete Address: 705 4th National Bank Bldg., Wichita, Kansas

Lease Name: Alford Well No. # 1

Location: C NW SE Sec. 35 Twp. 31 Rge. 8 (E) (W) W

County Harper Total Depth 4791 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Hall was instructed to plug the well as follows:

224' of 8 5/8" surface pipe, cement circulated with 160
sacks. Fill hole with mud to 180', 1st cementing plug,
1/4 sack hulls, cement with 20 sacks. Fill hole with mud
to 40', 2nd cementing plug, 1/2 sack hulls, Cement with 10
sacks to base cellar. Rat hole bridged and cemented with
2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent