



15-077-30067-0000

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

OCT 8 1965

10-8-65  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Don Rider of K & E Drilling, Inc. has this  
date requested permission to plug the following described well:

Mr. Rider guarantees payment of the plugging fee.

Operator's full Name: K & E Drilling, Inc.

Complete Address: 719 Union Center, Wichita, Kansas

Lease Name: Flowers Well No. # 1

Location: C SE SE SE Sec. 36 Twp. 31 Rge. 8 (E)(W) W

County Harper Total Depth 4762' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Rider was instructed to plug the well as follows:

244' of 8 5/8" surface pipe, cement circulated with 180 sacks.

Fill hole with drilling mud to 240', 2nd cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling mud

to 40', 2nd cementing plug, bridge with hulls, and cement with 10

sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent