

State of Kansas



15-077-20012-0000

State Corporation Commission

CONSERVATION DIVISION

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

RECEIVED
APR 28 1966
4-28-66
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Danny Biggs of Pickrell Drilling Company has this date requested permission to plug the following described well:

Mr. Biggs guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company

Complete Address: 705 Fourth National Bank Bldg., Wichita, Ks.

Lease Name: Warren "B" Well No. # 1

Location: C SE NW Sec. 32 Twp. 31 Rge. 8 (E)(W) W

County Harper Total Depth 4750' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Biggs was instructed to plug the well as follows:

204' of 8 5/8" surface pipe, cement circulated with 145 sacks. Fill hole with drilling mud to 200', 1st cementing plug, bridge with 1/4 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent