

State of Kansas



15-077-20298-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P. O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION

FEB 24 1975 2-24-75 CONSERVATION DIVISION Wichita, Kansas

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Crowe of DaMac Drlg Inc has this

date requested permission to plug the following described well:

Mr. Crowe guarantees payment of the plugging fee.

Operator's full Name: Petroleum Inc

Complete Address: 300 W Douglas Wichita, KS

Lease Name: Williams K Well No. 1

Location: C SE/NW Sec. 22 Twp. 31s Rge. 8 (E)(W) W

County: Harper Total Depth 4411 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Crowe was instructed to plug the well as follows:

209 ft 8 5/8 surface cemented with 175 sacks. Pump plug,

35 sacks cement to 200 ft. Mud to 40 ft, plug, 1/2 sack

hulls, 10 sacks cement to surface. 2 sacks cement in

rat hole. 2 sacks in mouse hole.

Pumped by Halliburton Cementing Great Bend, KS

Very truly yours,

[Signature] Conservation Division Agent