

1061184

2-1

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 165-21,452-0000

SE SE SE, SEC. 11, T 18 S, R 18 W/EX

330 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5027

Lease Name Nichols Well # 1

Operator: J.A. Allison

County Rush 12665

Name & Address 300 West Douglas, Suite 305

Well Total Depth 3897 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1233

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Woodman-Iannitti Drilling Company License Number 5122

Address P.O. Box 308, Great Bend, KS 67530

Company to plug at: Hour: 10:30 p.m. Day: 31 Month: 1 Year: 19 89

Plugging proposal received from Rich Wheeler

(company name) Woodman-Iannitti Drilling Company (phone) 316-792-1922

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1229-61'

1st plug at 1260' with 50 sx cement, 2nd plug at 630' with 30 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:15 a.m. Day: 1 Month: 2 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 1260' with 50 sx cement,

2nd plug at 630' with 30 sx cement,

3rd plug at 40-0' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

RECEIVED STATE CORPORATION COMMISSION

FEB 3 1989 2-2-89

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 2-8-89

Signed Paula A. Luthi (TECHNICIAN)

INV. NO. 23910

NOTICE OF INTENTION TO DRILL

(see rules on reverse side)

Expected Spud Date... January 15 1989

API Number 15-165-21,452-0000

OPERATOR: License # 5027
Name J. A. Allison
Address 300 West Douglas, Suite 305
City/State/Zip Wichita, Kansas 67202
Contact Person J. A. Allison
Phone 316-263-2241

SE SE SE Sec. 11 Twp. 18 S, Rg. 18
330 Ft. from South Line of Section
330 Ft. from East Line of Section

(Note: Locate well on Section Plat on reverse side)

Nearest lease or unit boundary line 330 feet
County RUSH

CONTRACTOR: License # 5122
Name Woodman-Iannitti Drilling Co.
City/State P.O. Box 308, Gt. Bend, KS 67530

Lease Name NICHOLS Well # 1
Ground surface elevation 2076 feet MSL

Well Drilled For: Oil Storage Infield Mud Rotary
Gas Inj Pool Ext Air Rotary
OWWO Expl Wildcat Cable

Domestic well within 330 feet: yes no
Municipal well within one mile: yes no

Depth to bottom of fresh water 358'
Depth to bottom of usable water 580'

Surface pipe by Alternate: 1 X 2
Surface pipe planned to be set 1196'

Conductor pipe required None
Projected Total Depth 3826 feet

Formation Arbuckle

If OWWO: old well info as follows:
Operator
Well Name
Comp Date Old Total Depth

I certify that well will comply with K.S.A. 55-101, et seq., plus eventually plugging hole to KCC specifications.
Date Dec 20, 1988 Signature of Operator or Agent J. A. Allison Title Operator

For KCC Use:
Conductor Pipe Required feet; Minimum Surface Pipe Required 600' feet per Alt.
This Authorization Expires 6-21-89 Approved By LKM/12-21-88

EFFECTIVE DATE: 12-26-88 ± 1200
Spool - 1-26-89

SE SE SE Sec. 11 Twp. 18 S, Rg. 18 X West

PLUGGING PROPOSAL IF ABOVE IS D & A

This plugging proposal will be reviewed and approved or revised at the time the district office is called prior to setting the casing (call 7 a.m. to 5 p.m. workdays).

RECEIVED
STATE CORPORATION COMMISSION

1st plug @ ft. deep 3826 w/35 SX or formation with Arbuckle feet of 2-2-89
2nd plug @ ft. deep 1221 w/35 SX or formation with thru D.P. Base Sur feet of FEB 2 1989
3rd plug @ ft. deep 60 w/25 SX or formation with circulated feet of
4th plug @ ft. deep 10 SX or formation with circ. in R/Hole feet of CONSERVATION DIVISION
5th plug @ ft. deep 10 SX or formation with in water well feet of Wichita, Kansas
(2) Rathole to surface minus 5 feet (b) Mousehole to surface minus 5 feet

PUSHER Rich Wheeler
TD 3897 FORMATION Arbuckle 3888
SURFACE PIPE 8 1/2 @ 1233
ANHYDRITE 1229 ELEVATION 1261
STARTING TIME & DATE 10:30 pm 1-31-89
COMPLETION TIME & DATE 1:15 am 2-1-89
1st PLUG @ 1260 FT. W/ 50 SX
2nd PLUG @ 630 FT. W/ 30 SX
3rd PLUG @ 40-0 FT. W/ 10 SX
4th PLUG @ FT. W/ SX
RAT HOLE CIRCULATED W/ 15'
MOUSE HOLE CIRCULATED W/ No
WATER WELL PLUGGED W/ No
CEMENT COMPANY Allied
TECHNICIAN R.A.
60/40w/67