

To: **STATE CORPORATION COMMISSION**
CONSERVATION DIVISION - PLUGGING SECTION App.
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5422
Operator: Abercrombie Drilling, Inc.
Name & Address 150 N. Main, Suite 801
Wichita, KS 67202

3-14 1892
API NUMBER 15- 165-21,555 -0000
NW NE SW, SEC. 11, T 18 S, R 18 W/E
2190 feet from S section line
3750 feet from E section line
Lease Name Herrman Well # 1
County Rush 126.06
Well Total Depth 3879 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 1250

Abandoned Oil Well Gas Well Input Well SMD Well O&A X

Other well as hereinafter indicated

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422
Address 150 N. Main, Suite 801, Wichita, KS 67202

Company to plug at: Hour: 8 p.m. Day: 14 Month: 3 Year: 19 91

Plugging proposal received from Tony Martin

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1232-62'

1st plug at 1250' with 50 sx cement,

2nd plug at 700' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 10 p.m. Day: 14 Month: 3 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug at 1250' with 50 sx cement,

2nd plug at 700' with 40 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement.

STATE CORPORATION COMMISSION

3-20-91
MAR 20 1991

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED
observe this plugging.

DATE APR 02 1991

INV. NO. 31254

Signed Glenn R. Barlow
(TECHNICIAN)

EFFECTIVE DATE: 3-9-91

FORM MUST BE TYPED

FORM C-1 4/90

State of Kansas

NOTICE OF INTENTION TO DRILL

Must be approved by the K.C.C. five (5) days prior to commencing well

FORM MUST BE SIGNED

ALL BLANKS MUST BE FILLED

Expected Spud Date ... 3 ... 5 ... 91 ...
month day year

OPERATOR: License # 5422
 Name: Abercrombie Drilling, Inc.
 Address: 150 N. Main, Suite 801
 City/State/Zip: Wichita, KS 67202
 Contact Person: Jerry A. Langrehr
 Phone: 316-262-1841

CONTRACTOR: License # 5422
 Name: Abercrombie Drilling, Inc.

Well Drilled For: Well Class: Type Equipment:

☒ Oil ... Inj ... Infield ... ☒ Mud Rotary
 ... Gas ... Storage ... Pool Ext. ... Air Rotary
 ... OWWO ... Disposal ... ☒ Wildcat ... Cable
 ... Seismic; ... # of Holes

If OWWO: old well information as follows:

Operator: N/A
 Well Name: _____
 Comp. Date: _____ Old Total Depth _____

Directional, Deviated or Horizontal wellbore? ... yes ☒ no
 If yes, total depth location: N/A

Apprx.
 NW NE SW Sec 11 Twp 18 S, Rg 18 ☒ East West

2190' feet from South line of Section
 3750' feet from East line of Section
 (Note: Locate well on Section Plat on Reverse Side)

County: Rush
 Lease Name: Herrman Well #: 1
 Field Name: Wildcat
 Is this a Prorated Field? ... yes ☒ no
 Target Formation(s): Arbuckle
 Nearest lease or unit boundary: 450
 Ground Surface Elevation: Approx. 2080 feet MSL
 Domestic well within 330 feet: ... yes ☒ no
 Municipal well within one mile: ... yes ☒ no
 Depth to bottom of fresh water: 300
 Depth to bottom of usable water: 550
 Surface Pipe by Alternate: 1
 Length of Surface Pipe Planned to be set: 1250
 Length of Conductor pipe required: none
 Projected Total Depth: 3900
 Formation at Total Depth: Arbuckle
 Water Source for Drilling Operations: unknown
 DWR Permit #: will file well ... farm pond ... other
 Will Cores Be Taken?: N/A ... yes ☒ no
 If yes, proposed zone: N/A

AFFIDAVIT

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Tony Martin
 SPUD DATE 3-6-91 INIT. _____
 LENGTH SURFACE PLANNED 1250' - 250'
 RESERVE PIT STATUS- REMOVE FLUID _____ LINED _____
 after salt sect. _____ bbls. when done bbls.
 RATHOLE AHEAD? Y _____ N _____ SIZE HOLE _____
 SURFACE PIPE 2 3/4" @ 1250' CONDUCTOR _____
 ANHYDRITE T- 1232 B- 1262 ELEVATION _____
 TD 3900 FORMATION Arbuckle
 RAN PIPE @ _____ DV TOOL _____ ALT II DONE _____
 _____ SX _____ Y _____ N _____
 _____ Arbuckle Plug @ _____ Ft. W/ 50 SX
 _____ Hug./Council @ _____ Ft. W/ _____ SX
 _____ Anhydrite Base @ 1250 Ft. W/ 50 SX
 _____ 1/2 Base Anyh. @ 700 Ft. W/ 40 SX
 _____ 1/2, 1/2 Plug @ _____ Ft. W/ _____ SX
 _____ Bottom Surface @ _____ Ft. W/ _____ SX
 _____ 40' Plug @ 40 Ft. W/ 10 SX
 RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ _____ SX
 WATER WELL _____ SX (Irr. Well _____ Pond _____)
 TECHNICIAN _____ G.B. DATE 3-11-91 Hauling _____
 TYPE OF CEMENT 60/40 pos 600/201
 STARTING TIME 8:00 (AM/PM) DATE 3-14-91
 COMPLETION TIME 10:00 (AM/PM) DATE 3-14-91
 CEMENT COMPANY Alled