

10-8

2-040747

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-077-20,529-0000

C S/2 SW NE, SECTION 22 TOWNSHIP 31 RANGE 8W

OPERATOR LICENSE # 5003 2970 FEET FROM S SECTION LINE
1980 FEET FROM E SECTION LINE

OPERATOR McCoy Petroleum Corp.
NAME & 110 S. Main, #500
ADDRESS Wichita, KS 67202

LEASE NAME: Williams C-2
COUNTY: Harper
WELL TOTAL DEPTH: 4390' 142.68

RECEIVED
KANSAS CORPORATION COMMISSION

DEC 30 1992
12-30-92
CONSERVATION DIVISION
WICHITA, KS

CONDUCTOR PIPE: _____

SURFACE CASING: 8-5/8" @ 249'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Shawnee Well Service
ADDRESS: Attica, KS LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1992

PLUGGING PROPOSAL RECEIVED FROM: Daryl Hanson
COMPANY NAME: McCoy Petroleum Corp. PHONE: _____

WERE: 5-1/2" @ 4382' - OH 4382-90' - CIBP @ 4350' & 2 sx -
35 sx 1200' - 35 sx 800' - circ cmt 300'

PLUGGING PROPOSAL RECEIVED BY: _____
PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART (_____) NONE (_____)

COMPLETED: HOUR: 1230 DAY: 8 MONTH: 10 YEAR: 1992

ACTUAL PLUGGING REPORT:
A CIBP was set @ 4350' to cover open hole - CIBP
capped w/2 sx cmt - 5-1/2" recovered from 3201' &
pulled to 1221' & 35 sx cmt spotted - 5-1/2" pulled to
816' & 35 sx cmt spotted - 5-1/2" pulled to 331' & cmt
circ to surf.

REMARKS: Howco #253987 60/40 4% gel

INVOICED
I WILL OBSERVE THIS PLUGGING.

DATE 1-5-93

WEL. NO. 37100

15/
Steve Van Gieson (AGENT)