

2-11

2-040613 ²⁵²
R

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

API NUMBER: 15-077-20487-0000

SE NW SE, SECTION 22 TOWNSHIP 31 RANGE 8W

OPERATOR LICENSE # 5003

1650 FEET FROM S SECTION LINE
1650 FEET FROM E SECTION LINE

OPERATOR McCoy Petroleum Corp.
NAME & 110 S. Main, #500
ADDRESS Wichita, KS 67202

LEASE NAME: Williams #B-2
COUNTY: Harper

WELL TOTAL DEPTH: 4405' 143.16

CONDUCTOR PIPE: _____ " @ _____'

SURFACE CASING: 8-5/8" @ 239'

ABANDONED OIL WELL _____ GAS WELL X INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Hays Well Service
ADDRESS: Attica, KS LICENSE: _____

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Daryl Hanson
COMPANY NAME: McCoy Petroleum Corp PHONE: _____

WERE: 4-1/2" 4391' - OH 4391-4405' - CIBP 4350' - 35 sx
1360' - 35 sx 900' - circ 289'

PLUGGING PROPOSAL RECEIVED BY: Steve Van Gieson

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (_____) PART (X) NONE (_____)

COMPLETED: HOUR: 16:30 DAY: 11 MONTH: 2 YEAR: 1991

ACTUAL PLUGGING REPORT:

The open hole shut off by setting CIBP at 4345' &
capped w/2 sx cmt - 4-1/2" shot loose at 2830' and
pulled to 1347' and 35 sx cmt spotted - 4-1/2" pulled
to 915' and 35 sx cmt spotted in place - 4-1/2" pulled
to 288' and cmt circ to surf.

REMARKS: Howco #097453 40/60 4% gel

I DID OBSERVE THIS PLUGGING.

INVOICED

MAR 05 1991

DATE

CP-213

FEB 26 1991

INV. NO.

30999

CONSERVATION DIVISION
Wichita, Kansas

Steve Van Gieson
Steve Van Gieson (AGENT)

FORM
REV. 3/90

DW