

To: ² 040377
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-2-87
API NUMBER 15- 077-20,495-0008
NW SW SE, SEC. 22, T 31 S, R 8 WXX
990 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003

Operator: McCoy Petroleum
Name & Address: 110 S. Main, Suite 500
Wichita, KS 67202

Lease Name Williams Well # B#3
County Harper 143.78
Well Total Depth 4424 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 272

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Hayes Well Service License Number _____
Address Attica, KS

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Darral Hanson
(company name) McCoy Petroleum (phone) _____
were: CIBP @4375' and 3 sxs Recover 4 1/2"

Plugging Proposal Received by District #2 Office
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 10:15 Day: 2 Month: 12 Year: 19 87

ACTUAL PLUGGING REPORT A cast iron bridge plug was set @4355' and capped with 3 sxs cement. The 4 1/2" was shot off and recovered from 2168'. The top was squeeze plugged by pumping 300# hulls, 15 sxs gel and 120 sxs 60/40 poz, 2% gel.

Remarks: Howco #623142

(If additional description is necessary, use BACK of this form.)

INVOICED RECEIVED
DATE 12-8-87 Signed [Signature]
INV. NO. 19227 (TECHNICIAN)

DEC 7 1987
12-7-87
CONSERVATION DIVISION
Wichita, Kansas

12-2 JAN 14 1988