

2040076

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-077-20479-0000

NW/NE/SE4 SEC. 22, T. 31 S, R. 8 (W)

TECHNICIAN'S PLUGGING REPORT 3-23-84

_____ feet from N/S section line

_____ feet from W/E section line

Operator License # 50036 5003

Lease Name Williams Well # B-1

Operator: M. Coy Rev. & Ins. Corp.

County Harper

Name & Address Roger McCoy

Well Total Depth 4391 142.91 feet

500 Heritage Park Place

Conductor Pipe: Size _____ feet

Wichita Ks 67202

Surface Casing: Size 8 5/8 feet 258

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clark Corporation License Number 5105

Address 107 W. Fowler Medicine Lodge Ks. 67104

Company to plug at: Hour: _____ Day: _____ Month: _____ Year: 19 _____

Plugging proposal received from Elmo Morganstein

(company name) Clark Corporation (phone) _____

were: Sand to 4328' 5.5x

5 1/2 4378' Pull Pipe

13' of Open Hole Top with 3 Hull, 6 gel 100 60/40 3% 2%

Plugging Proposal Received by Stan Marcotte
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 1000 Day: 7 Month: 3 Year: 19 84

ACTUAL PLUGGING REPORT The Bottom of the hole was filled with sand to 4328' and 5 sacks of cement was spotted on top of sand thru the Bailer. The pipe was shot off, and 3500' of 5 1/2 was recovered.

The Top was plugged with 3 sacks of Hull, 6 sacks of gel and 100 sack of 60/40 Poz-mix cement 3% ca 2% gel by

Remarks: Sun Cementing # 18054 Max. Press 600# Shut-in Press 450
(If additional description is necessary, use BACK of this form.)

INVOICE

(did or did not) observe this plugging.

DATE 3-23-84

Signed Stan Van Guren
(TECHNICIAN)

INV. NO. 0905