

2-040813

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
130 S. Market, Room 2078
Wichita, Kansas 67202

9-20

API NUMBER: 15-077-20,515-0000
NW, SE, SE, SECTION 22 TOWNSHIP 31 RANGE 08W

OPERATOR LICENSE # 5003 990 FEET FROM S SECTION LINE
990 FEET FROM E SECTION LINE

OPERATOR McCOY PETROLEUM CORP.
NAME & 3017 N. CYPRESS
ADDRESS WICHITA, KS 67223

LEASE NAME: LEEPER "A" #1
COUNTY: HP Harper
WELL TOTAL DEPTH: 4417 143.55

PIPE: _____

SURFACE CASING: 8 5/8" @ 256'

ABANDONED OIL WELL GAS WELL _____ INPUT WELL _____ SMD _____ D&A _____

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: SHAWNEE WELL SERVICE
ADDRESS: ATTICA, KS LICENSE: 30346

COMPANY TO PLUG AT: HOUR: _____ DAY: _____ MONTH: _____ YR: 1995

PLUGGING PROPOSAL RECEIVED FROM: JANA COREEN
COMPANY NAME: McCOY PETROLEUM CORP. PHONE: _____
WERE: 4 1/2" @ 4409', OH 4409-4417'. SAND TO 4360' AND 4 XS.
SHOOT PIPE. 35 XS. @ 1350', 35 XS. 900'. CIRC. 300'.

PLUGGING PROPOSAL RECEIVED BY: _____

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 10:00 DAY: 20 MONTH: 9 YEAR: 1995

ACTUAL PLUGGING REPORT:

A CIBP WAS SET @ 4350' AND CAPPED WITH 2 XS. CMT.
PIPE RECOVERED FROM 3000' AND PULLED TO 1358' WHERE 35
XS. CMT. WAS SPOTTED. PULLED PIPE TO 877' WHERE 35 XS.
CMT. WAS SPOTTED. PULL PIPE TO 319' WHERE CMT. WAS
CIRC. TO SURFACE.

REMARKS: ALLIED CMT. 60/40 4% GEL.

I DID OBSERVE THIS PLUGGING.

Steve Van Gieson
Steve Van Gieson (AGENT)

FORM CP-2/3
REV. 3/90

INVOICED

DATE 10-12-95
INV. NO. 43750

RECEIVED
KANSAS CORPORATION COMMISSION

OCT 11 1995
10-11-95
CONSERVATION DIVISION
WICHITA, KS