

To: 1051191
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

8-4
API NUMBER 15-⁰⁹⁶20,102 0000

SE SE SE, SEC. 19, T 26 S, R 29 W/E

330 feet from S section line

330 feet from E section line

Lease Name Bleumer-Ardery Well # 19-16

County Gray 165.10

Well Total Depth 5080 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 450

TECHNICIAN'S PLUGGING REPORT

Operator License # 4762

Operator: Christensen Engineering

Name & Address P.O. Box 1937

Wichita, KS 67201

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Plains Inc. License Number 4072

Address P.O. Box 346, Ness City, KS 67560

Company to plug at: Hour: 11 a.m. Day: 4 Month: 8 Year: 19 89

Plugging proposal received from Clint Base

(company name) Plains, Inc. (phone) 913-798-3995

were: 4 1/2" at 5071' PBTD 5026' Perfs at 4994-5002' Elevation 2759' GL Anhydrite at 1800'

1st plug sand back to 4940' and dump 4 sx cement on top of sand through bailer,

2nd plug perforate at 1800' and pump approx. 400 sx cement.

Plugging Proposal Received by Steve Durrant
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:50 p.m. Day: 4 Month: 8 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4950' and dumped 4 sx cement on top of

sand through bailer,

2nd plug perforated 4 1/2" at 1800', pumped 110 sx cement down 4 1/2".

Maximum pressure 1600 psi and shut in 300 psi.

3rd plug pumped 75 sx cement down 4 1/2" X 8 5/8" annulus.

Maximum pressure 600 psi and shut in 600 psi.

Remarks: Used ATL cement by Allied. No casing recovery.
(If additional description is necessary, use BACK of this form.)

RECEIVED
STATE CORPORATION COMMISSION
AUG 8 1989
8-08-1989
CONSERVATION DIVISION
Wichita, Kansas

INVOICED observe this plugging.

Signed Richard M. Lacey
(TECHNICIAN)

DATE 8-9-89

INV. NO. 25591