

1 090330

API NUMBER 15- 069-20,106 0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C SE NE SE, SEC. 19; T 26 S, R 29 W/E
1650 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6975

Lease Name Blumer-Ardrey Well # 19-9

Operator: Gary-Williams Oil Producer, Inc.

County Gray 167.51

Name & Address 115 Inverness Drive Ease

Well Total Depth 5154 feet

Englewood, CO 80112

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 507

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address Box 506, Liberal, KS 67901

Company to plug at: Hour: 9:00 am Day: 2 Month: May Year: 19 85

Plugging proposal received from Ray Hager

(company name) Gary-Williams (phone) 303-799-3800

were: 4 1/2" at 5153' Perfs at 4984-97', Anhydrite at 2664'

1st plug set CIBP at 4925' with 2 sx cement

Balance plugs with mud and spot through 4 1/2" casing.

2nd plug at 850' with 50 sx cement

3rd plug at 550' with 40 sx cement
solid bridge

4th plug bulls - plug at 40' Plugging Proposal Received by Robert B. Tarbutton
cement to surface with 10 sx cement (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 3:00 pm Day: 2 Month: May Year: 19 85

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4295' with 2 sx cement, 2nd plug at 850' with

50 sx cement, 3rd plug at 550' with 40 sx cement, 4th & 5th plugs - solid bridge - bulls -
plug at 40' -- cement to surface with 10 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1985
5-13-1985
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Recovered 868' 4 1/2" casing. Used common cement by Sargent's

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 5-14-85

Signed Robert B. Tarbutton (TECHNICIAN)

INV. NO. 8117

JUN 6 1985