

1 070867

10-20

120

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 203-20,094-0000

SW NE SE, SEC. 35, T 20 S, R 35 W/E
1650 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5393

Lease Name Moody Well # 2

Operator: A.L. Abercrombie, Inc.
Name & Address: 150 N. Main, Suite 801
Wichita, KS 67202

County Wichita 165.10

Well Total Depth 5080 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 226

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 150 N. Main, Suite 801, Wichita, KS 67202

Company to plug at: Hour: 10 a.m. Day: 20 Month: 10 Year: 19 90

Plugging proposal received from Bill Craig

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at Base Anhydrite with 50 sx cement, 2nd plug at 1350' with 80 sx cement,

3rd plug at 300' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 12:15 p.m. Day: 20 Month: 10 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug at 2250' with 60 sx cement,

2nd plug at 1300' with 80 sx cement,

3rd plug at 260' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement,

6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED If not observe this plugging.

Signed Dan Goodrow (TECHNICIAN)

DATE 10-30-90

INV. NO. 29781
10-20