

To: 1 120776 3-3
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 203-20,098 -0000
SE NE SW, SEC. 34, T 20 S, R 35 W/E
1650 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5003
Operator: McCoy Petroleum Corp.
Name & Address: 110 S. Main, Ste. 500
Wichita, KS 67202

Lease Name Wilken "A" Well # 1-34
County Wichita
Well Total Depth 5080 165.10 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 385

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Sweetman Drilling, Inc. License Number 5658
Address 110 S. Main, Ste. 500, Wichita, KS 67202

Company to plug at: Hour: 4 P.m. Day: 3 Month: 3 Year: 19 93

Plugging proposal received from Eugene Saloga
(company name) Sweetman Drilling, Inc. (phone) 316-265-9697

was: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2262-75'
1st plug at 2280' with 50 sx cement, 2nd plug at 1140' with 50 sx cement,
3rd plug at 600' with 80 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None x
Operations Completed: Hour: 9 P.m. Day: 3 Month: 3 Year: 1993

ACTUAL PLUGGING REPORT 1st plug at 2280' with 50 sx cement,
2nd plug at 1140' with 50 sx cement,
3rd plug at 600' with 80 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

RECEIVED
CORPORATION COMMISSION
MAR 8 1993
3-8-93
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Halliburton.
Additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.
DATE: 3-18-93

Signed Duane Rankin (TECHNICIAN)

INVOICED
37484
3-3