

1 050840

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-203-20,045-0000
C SE SW, SEC. 34, T 20 S, R 35 W/4
660 feet from S section line
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5027
Operator: J. A. Allison
Name & Address 300 West Douglas, Ste. 305
Wichita, KS 67202-2975

Lease Name Wilken Well # 1
County Wichita 163.02
Well Total Depth 5016 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 331

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3:30 pm Day: 6 Month: August Year: 19 86

Plugging proposal received from Vernon Duntz

(company name) Kelso Casing Pulling, Inc. (phone) (316) 938-2457

were: 5 1/2" at 4689' PBTD at 4616' Perfs at 4502-16'

1st plug sand back to 4450' and dump 5 sx cement on top of sand through bailer

2nd plug pump down 8 5/8 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack

hulls, 8 5/8 wiper plug and 150 sx cement.

Plugging Proposal Received by Paul A. Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 4:30 pm Day: 6 Month: August Year: 1986

ACTUAL PLUGGING REPORT 1st plug sanded bottom back to 4450' and dumped 5 sx cement on

top of sand through bailer, 2nd plug pumped down 8 5/8 with 3 sx hulls, 15 sx gel,

50 sx cement, 10 sx gel, 1 sack hulls, 8 5/8 wiper plug and 150 sx cement.

Maximum pressure 500 psi and shut in 50 psi.

Remarks: Recovered 300' of 5 1/2" casing. Used 60/40 Pozmix with 6% gel pumped by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED

DATE AUG 12 1986
INV. NO. 14703
8-6

8-12-86
AUG 12 1986

Signed Richard W. Ludy
(TECHNICIAN)