

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-203-20084-00-00  
Spot: CSESW Sec/Twnshp/Rge: 33-20S-35W  
660 feet from S Section Line, 3300 feet from E Section Line  
Lease/Unit Name: MCMICHAEL Well Number: 4  
County: WICHITA Total Vertical Depth: 4630 feet

Operator License No.: 5449  
Op Name: GREAT PLAINS RESOURCES, INC.  
Address: PO BOX 369  
LITTLETON, CO 80160

Conductor Pipe: Size \_\_\_\_\_ feet: 8/50.48  
Surface Casing: Size 8.625 feet: 401 WITH 250 SX CMT  
Production: Size 5.5 feet: 4600 WITH 200 SX CMT  
Liner: Size \_\_\_\_\_ feet: \_\_\_\_\_

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 05/16/2002 8:45 AM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 278-2026

Proposed Plugging Method: 1ST PLUG AT 2200' WITH 50 SX CMT. 2ND PLUG AT 1100' WITH 80 SX CMT. 3RD PLUG AT 430' WITH 50 SX CMT. 4TH PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 05/16/2002 10:00 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:  
PBTD 4600'. PERFS AT 4534-38 & 4515-18'. BOTTOM PERF SQUEEZED WITH 20 SX CMT AT 4470'. 1ST PLUG PULLED TO 1100' AND PUMPED 10 SX GEL & 80 SX CMT. 2ND PLUG PULLED TO 430' & PUMPED 50 SX CMT. 3RD PLUG PULLED TO 40' & PUMPED 10 SX CMT.

RECEIVED  
MAY 24 2002  
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1123' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Kevin D Strube  
(TECHNICIAN)

INVOICED  
DATE 5-28-02  
VV. NO. 2002061847  
5-20-02  
MAY 20 2002  
MP

Form 9-23