


Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH

Locate well correctly on above
Section Plat

Rush County. Sec. 35 Twp. 18S Rge. 18W (E) (W)
Location as "NE/CNW/SW" or footage from lines NE NW SE
Lease Owner Halliburton Oil Producing Co.
Lease Name Mix Well No. 1
Office Address 2915 Classen Blvd., Oklahoma City, Okla. 73106
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed October 10 19 70
Application for plugging filed October 10 19 70
Application for plugging approved October 10 19 70
Plugging commenced October 10 19 70
Plugging completed October 10 19 70
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced?

Name of Conservation Agent who supervised plugging of this well Leo F. Massey, Hays, Kansas
Producing formation Depth to top Bottom Total Depth of Well 3892 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	390'	8 5/8"	390'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug: 520'/50 sacks cement
370'/25 sacks cement
40'/10 sacks cement

RECEIVED
STATE CORPORATION COMMISSION
OCT 16 1970
15-1165-70
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Hellar Drilling Company, Inc.
Address 339 Union Center Bldg., Wichita, Kansas 67202

STATE OF Kansas COUNTY OF Sedgwick
D. L. Hellar, President of Hellar Drilg. Co. Inc., ss.

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) D. L. Hellar, President
339 Union Center Bldg., Wichita, Kansas 67202

(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of October, 1970

March 25, 1972

Notary Public.



DRILLER'S LOG

COMPANY: Halliburton Oil Producing Co., 2915 Classen Blvd.
Oklahoma City, Okla. 73106

CONTRACTOR: Hellar Drilling Company, Inc., Wichita, Kansas 67202

LEASE: #1 Mix

LOCATION: NE NW SE 35-18S-18W, Rush County, Kansas

COMMENCED: September 29, 1970

COMPLETED: October 10, 1970

CASING: Set 8 5/8" Surface Casing @ 390'/235 sacks cement

0-70	Post Rock
70-970	Shale & Sand
970-1183	Red Bed & Shale
1183-1213	Anhydrite
1213-1217	Red Bed
1217-2000	Shale & Red Bed
2000-3085	Lime & Shale
3085-3175	Lime (Topeka)
3175-3275	Lime & Shale
3275-3360	Lime
3360-3490	Lime & Shale
3490-3740	Lime
3740-3805	Lime & Shale
3805-3842	Arbuckle
3842-3892	Lime
3892	Rotary Total Depth

D & A

RECEIVED
STATE CORPORATION COMMISSION
OCT 16 1970
10-16-70
CONSERVATION DIVISION
Wichita, Kansas

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

I, D. L. Hellar, do hereby certify that the above and foregoing is a true and correct copy of the log of the #1 Mix, located in NE NW SE 35-18S-18W, Rush County, Kansas, as reflected by the files of the Hellar Drilling Company, Inc.

HELLAR DRILLING COMPANY, INC.

By *D. L. Hellar*
President - D. L. Hellar

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas, this 15th day of October, 1970.

Catherine Darcey
Notary Public - Catherine Darcey

My Commission Expires:
March 25, 1972.