

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-165-21,624-0000

LEASE NAME Herman

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1

990' Ft. from S Section Line

4290' Ft. from E Section Line

SEC. 11 TWP. 18S RGE. 18 (E) or (W)

COUNTY Rush

LEASE OPERATOR Carmen Schmitt, Inc.

ADDRESS P.O. Box 47, Great Bend, KS 67530

PHONE# (316) 793-5100 OPERATORS LICENSE NO. 6569

Date Well Completed _____

Character of Well D&A

Plugging Commenced 12-10-92

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-10-92

The plugging proposal was approved on 12-10-92 (date)

by Richard Lacey (KCC District Agent's Name).

Is AC0-1 filled? No If not, is well log attached? _____

Producing Formation Arbuckle Depth to Top _____ Bottom T.D. 3895'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	221'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

Fill w/heavy mud; set 1st plug @ 3840'-3640' w/50 sx; 2nd plug @ 1260'-1060' w/50 sx; 3rd plug @ 600'-400' w/50 sx; 4th plug @ 250'-90' w/40 sx; 5th plug @ 40'-surface w/10 sx; rathole 15 sx; Total 215 sx 60-40 posmix 6% gel 1/2# Flocel per sx.

(If additional description is necessary, use BACK of this form.)


Name of Plugging Contractor Abercrombie RTD, Inc. License No. 30684

Address 150 N. Main, Suite 801, Wichita, KS 67202

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Carmen Schmitt, Inc.

STATE OF Kansas COUNTY OF Sedgwick, ss.

Jack K. Wharton (Employee of Operator of above-described well, being first duly sworn on oath, says: That I have knowledge of the statements, and matters herein contained and the log of the above-described well as filed the same are true and correct, so help me God.



(Signature) Jack K. Wharton
(Address) 150 N. Main, Suite 801, Wichita, Kansas

SUBSCRIBED AND SWORN TO before me this 28th day of December, 19 92

C. Douglas Steadard
Notary Public

My Commission Expires: March 20, 1993

1-19-93
RECEIVED
STATE CORPORATION COMMISSION
JAN 19 1993
CONSULTATION DIVISION
WICHITA, KANSAS