

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Harper County, Sec. 5 Twp. 31 Rge. 9 1/2 (E) (W)

Location as "NE, CN, W, SW, SE" or footage from lines: C E/2 E/2 SE  
Lease Owner: E.K. Edmiston

Lease Name: Cox Well No. B-1  
Office Address: 405 First Natl Bank Bldg., Wichita, Ks. 67202

Character of Well (completed as Oil, Gas or Dry Hole): Gas & Oil

Date well completed: Nov. 13, 19 65

Application for plugging filed: Sept. 5, 19 74

Application for plugging approved: Sept. 6, 19 74

Plugging commenced: September 13, 19 74

Plugging completed: September 19, 19 74

Reason for abandonment of well or producing formation: below economic level

If a producing well is abandoned, date of last production: Sept. 13, 19 74

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well: Russell Biberstein

Producing formation: \_\_\_\_\_ Depth to top: \_\_\_\_\_ Bottom: \_\_\_\_\_ Total Depth of Well: 4490 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	275	None
				4 1/2	4490	3627

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

- Dump sand from 4490 to 4420'
- 4 sacks of cement dumped with dump bailer
- Cement from 4420 to 4400'
- Ripped pipe at 4000-3900-3800-3700-3627
- Wood bridge at 315
- Rock from 315 to 305
- 5 yards of ready mix

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 10 1974  
CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor: Clarke Corporation #583  
Address: Box 187, Medicine Lodge, Kansas 67104

STATE OF KANSAS COUNTY OF BARBER, ss.

Edmo R. Morgenstern (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Edmo R. Morgenstern  
Medicine Lodge, Kansas (Address)

AND SWORN TO before me this 1st day of October, 19 74

April 4, 1978  
Jessie Hamilton  
Notary Public.



DRILLER'S LOG

Operator: E. K. Edmiston  
425 First National Bank Building  
Wichita, Kansas 67202

Rotary Drilling Commenced: November 3, 1965

Rotary Drilling Completed: November 13, 1965

Well Name: COX "B" No. 1  
c E/2 E/2 SE/4 5-31S-9W  
Harper County, Kansas

Contractor: E. K. Edmiston Drilling Co., Inc.  
425 First National Bank Building  
Wichita, Kansas 67202

Casing Record: 244 feet of 8-5/8" with 200 sacks cement  
4 1/2" on bottom at 4490' with 125 sacks  
cement

L O G

Sand	0 - 158
Sand and Shale	244
Shale and Red Bed	1090
Shale	1255
Shale and Lime	1635
Lime and Shale	2130
Shale and Lime	2920
Lime and Shale	3120
Lime and Shale	3710
Lime	4490 RTD
(all measurements from Kelly bushing)	


RECEIVED  
STATE CORPORATION COMMISSION

SEP 6 1964

CONSERVATION DIVISION  
Wichita, Kansas

The undersigned, E. K. Edmiston, President of E. K. Edmiston Drilling Co., Inc., hereby certifies on behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well, as reflected by the daily drilling reports.


E. K. EDMISTON DRILLING CO., INC.

By   
E. K. Edmiston, President

STATE OF KANSAS,  
SS:  
SEDGWICK COUNTY,

BE IT REMEMBERED that on this 17th day of November, 1965, before me, the undersigned, a Notary Public in and for said county and state, appeared E. K. EDMISTON known to me to be the same person who executed the foregoing instrument as President and on behalf of the E. K. Edmiston Drilling Co., Inc., and he duly acknowledged the execution of the same for himself and for said company.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal on the day and year last above written.

  
A. B. Bagen, Notary Public

My commission expires  
August 25, 1968