

15-077-20501-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Harper County. Sec. 5 Twp. 31S Rge. 9 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
NE NE NE

Lease Owner Edmiston Oil Co., Inc.
Lease Name Cox "B" Well No. 3
Office Address 800 Vickers-KSB&T Building, Wichita, KS 67202
Character of Well (Completed as Oil, Gas or Dry Hole)

Dry Hole

Date Well completed November 17 1978
Application for plugging filed November 17 1978
Application for plugging approved November 17 1978
Plugging commenced November 17 1978
Plugging completed November 17 1978
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen
Producing formation Depth to top Bottom Total Depth of Well 4470'
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	211'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mudded up with heavy mud to 210'. Followed by 40 sacks of cement pumped through drill pipe with pump truck. Pushed plug and 1/2 sack of hulls to 40' and pumped 12 sacks of cement through drill pipe with pump truck to base of well cellar. Plugged rat hole with 3 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1978

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Co., Inc.
910 Union Center, Wichita, Kansas 67202


STATE OF KANSAS COUNTY OF SEDGWICK, ss.
John C. Graves (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves
910 Union Center, Wichita, KS 67202

(Address)
November 21st day of November, 1978

SUBSCRIBED AND SWORN TO before me this 21st day of November, 1978
NOTARY PUBLIC
My commission expires January 18, 1982

Dorothy Galbraith
Dorothy Galbraith Notary Public.



ROTARY DRILLERS LOG

OPERATOR: Edmiston Oil Co., Inc.
800 Vickers-KSB&T Building
Wichita, Kansas 67202

DRILLING COMPLETED: November 9, 1978

CONTRACTOR: Graves Drilling Co., Inc.
910 Union Center
Wichita, Kansas 67202

DRILLING COMPLETED: November 17, 1978

CASING RECORD: 5 Jts. 211' of new 8-5/8"
cemented with 235 sacks

LOCATION: Cox "B" No. 3
NE NE NE
Section 5-31S-9W
Harper County, Kansas

0	-	130	Sand
130	-	211	Red Bed
211	-	859	Red Bed and Shale
859	-	2140	Shale and Lime
2140	-	2300	Lime and Shale
2300	-	2783	Shale and Lime
2783	-	3240	Lime and Shale
3240	-	3444	Shale and Lime
3444	-	3659	Shale and Lime and Sand
3659	-	3860	Shale and Lime
3860	-	4017	Lime
4017	-	4291	Lime and Shale
4291	-	4382	Shale and Lime
4382	-	4418	Lime and Chert
4418	-	4470	Lime
		4470	Rotary Total Depth

RECEIVED
STATE CONSERVATION COMMISSION
NOV 27 1978
CONSERVATION DIVISION
Wichita, Kansas


I hereby certify the foregoing statements to be true and correct to the best of my knowledge.

GRAVES DRILLING CO., INC.

By John Graves
President

STATE OF KANSAS)
) SS.
COUNTY OF SEDGWICK)

Subscribed and sworn to before me, a Notary Public, this 21st day of November, 1978.



My commission expires: January 18, 1982

Dorothy Galbraith
Dorothy Galbraith Notary Public