

5-23

To: 1 070811
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 203-20,048-0000
C NW SE, SEC. 34, T 20 S, R 35 W/E
1980 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5027
Operator: J.A. Allison
Name & Address 300 West Douglas, Suite 305
Wichita, KS 67202-2975

Lease Name Downs Well # 3
County Wichita 162.50
Well Total Depth 5000 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 577

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 23 Month: 5 Year: 19 90

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 5 1/2" at 4677' PBD 4640' Perfs at 4507-24'

1st plug sand back to 4450' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 175 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 2 p.m. Day: 23 Month: 5 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug sanded back to 4450' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, and 175 sx cement.

Maximum pressure 500 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2015' of 5 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 5-30-90
INV. NO. 28278

STATE CORP. COMMISSION
MAY 29 1990
5-29-90

Signed Dan Goodrow (TECHNICIAN)