

State of Kansas



15:135-201380000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 17 1968
CONSERVATION DIVISION
Wichita, Kansas
4-17-68

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Steincamp of Strata Drlg. has this

date requested permission to plug the following described well:

Mr. Steincamp guarantees payment of the plugging fee.

Operator's full Name: Prospect Oil, Inc.

Complete Address: 811 Union Center Bldg., Wichita, Ks.

Lease Name: Fehrenbach Well No. 1

Location: NE NE Sec. 23 Twp. 20 Rge. 25 (E)(W) X

County Ness Total Depth 4460' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Steincamp was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 1550' and displace
100 sc cement thru drill pipe. Heavy mud to 280' set cementing plug and
displace 25 sc cement thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sc hulls and 10 sc cement to base of cellar. Plug rat hole
with 2 sc cement.

Very truly yours,

Leo G. Massey
Conservation Division Agent