



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Steincamp of Strata Drlg.

date requested permission to plug the following described well:

Mr. Steincamp guarantees payment of the plugging fee.

Operator's full Name: Strata Drlg., Inc.

Complete Address: P. O. Box 355 Great Bend, Ks.

Lease Name: Roth Well No. 1

Location: C SE SE Sec. 20 Twp. 20 Rge. (E)(W) 25

County: Ness Total Depth 4480 Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Steincamp was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 720' and displace
70 sk cmt thru drill pipe. Heavy mud to 270' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing
plug, 1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Boyd L. Massey
Conservation Division Agent

5-11-70
RECEIVED
STATE CORPORATION COMMISSION
MAY 11 1970
CONSERVATION DIVISION
Wichita, Kansas