



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 7 1966
2-7-66
CONSERVATION DIVISION
WICHITA, KANSAS

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Irvin Neighbors of Tom-Kat, Inc. has this

date requested permission to plug the following described well:

Mr. Neighbors guarantees payment of the plugging fee.

Operator's full Name: Tom-Kat, Inc.

Complete Address: 1127 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Schiff Well No. # 1

Location: NE SW NW Sec. 11 Twp. 32 Rge. 11 (E) (W) W

County Barber Total Depth 4450' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Neighbors was instructed to plug the well as follows:

240' of 8 5/8" surface pipe, cement circulated with 200 sacks.

Fill hole with drilling mud to 240', 1st cementing plug, bridge

with hulls, and cement with 25 sacks. Fill hole with drilling mud

to 40', 2nd cementing plug, bridge with hulls, and cement with 10

sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Ebling
Conservation Division Agent