

15-165-20359-0000

CR2

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Sanders of Pubco Petr. has this date requested permission to plug the following described well:

Mr. Sanders guarantees payment of the plugging fee.

Operator's full Name: Pubco Petroleum Corporation

Complete Address: Box 567 McCook, Nebraska

Lease Name: Westermyer Well No. 30 - 13

Location: C SW SW Sec. 30 Twp. 19 Rge. (E)(W) 20

County: Rush Total Depth 4498' Oil Well

Gas Well Input Well SWD Well D & A XX Lost Hole

Mr. Sanders was instructed to plug the well as follows:
Gun pits, circulate heavy mud, set cementing plug at 600' and displace
70 sk cmt thru drill pipe. Heavy mud to 300' set cementing plug and
displace 20 sk cmt thru drill pipe. Heavy mud to 40' set cementing plug,
1/2 sk hulls and 10 sk cmt to base of cellar.

Very truly yours,

Bo F. Messing
Conservation Division Agent