



*CPA*

15:135-21027-0000

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION

APR 1 1975  
4-1-75  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Engle of Slawson Drlg. has this

date requested permission to plug the following described well:

Mr. Engle guarantees payment of the plugging fee.

Operator's full Name: Donald C. Slawson

Complete Address: 408 One Twenty Bldg., Wichita, Ks.

Lease Name: Nelson "R" Well No. 1

Location: NW NE SE Sec. 3 Twp. 16 Rge. (E)(W) 26

County: Ness Total Depth 4590' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Engle was instructed to plug the well as follows:

Gun pits, circulate Heavy mud, set 70 sk cmt plug at 800' thru drill

pipe. Heavy mud to 240' set 20 sk cmt plug thru drill pipe. Heavy mud

to 40' set solid bridge & 10 sk cmt plug to base of cellar.

Very truly yours,

Leo H. Massey  
Conservation Division Agent