

1 070241

14 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23.060-6600
NE NE NE, SEC. 30, T 16 S, R 23 W/E XX

TECHNICIAN'S PLUGGING REPORT

4950 feet from S section line
330 feet from E section line

Operator License # 5267

Lease Name Mast Well # 1

Operator: K & E Petroleum, Inc.
Name & Address 100 S. Main, Suite 300
Hardage CTR. N.

County Ness
Well Total Depth 4575 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 259

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 9:50 a.m. Day: 6 Month: 11 Year: 19 86

Plugging proposal received from Harold Maley

(company name) Abercrombie Drilling, Inc. (phone) 913-674-5768

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2498' GL
Anhydrite 1856-90'

1st plug at Base Anhydrite with 40 sx cement,

2nd plug at Base Cheyenne with 80 sx cement,

3rd plug at 30' below base surface casing with 50 sx cement,

4th plug at 40' with 10 sx cement, 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All x Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 6 Month: 11 Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 1890' with 50 sx cement,

2nd plug at 1100' with 80 sx cement,

3rd plug at 290' with 50 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 11-12-86

INV. NO. 15328

11-6

Signed Dan Goodrow
(TECHNICIAN)

11-10-86