

1 090058

3-23

161 P

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23438-6000
C SW NW SEC. 29, T 16 S, R 23 W

3300 feet from S section line
4620 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5565

Lease Name Mishler Well # 1

Operator: National Cooperative Refinery
Name & Address: 1775 Sherman Street
Suite 3000
Denver, CO 80203

County Ness 149.50
Well Total Depth 4600' feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 357'

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling Inc. License Number 5422

Address 801 Union Center Wichita, KS 67202

Company to plug at: Hour: 6:00 AM Day: 23 Month: 3 Year: 19 90

Plugging proposal received from Jony Martin

(company name) Abercrombie Drilling, Inc. (phone) 316-262-1841

were: To fill hole with heavy mud and spot cement through
drill pipe. 1st plug at 1895' with 50 s/w cement, 2nd plug at 915'
with 80 s/w cement, 3rd plug at 390' with 40 s/w cement, 4th plug at
40' with 10 s/w cement, and 5th plug to circulate rat hole
with 15 s/w cement. Anhydrite 1857' to 1892' ELEV = 2505'

Plugging Proposal Received by Michael R Wilson
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 9:15 AM Day: 23 Month: 3 Year: 19 90

ACTUAL PLUGGING REPORT Filled hole with heavy mud and spotted
cement through drill pipe. 1st plug at 1895' with 50 s/w cement,
2nd plug at 915' with 80 s/w cement, 3rd plug at 390' with 40 s/w
cement, 4th plug at 40' with 10 s/w cement, and 5th plug circulated
rat hole with 15 s/w cement.

Remarks: Used 60/40 Pomix w/ 6% gel by Halliburton
(if additional description is necessary, use BACK of this form.)

INVOICED Reserve this plugging.

DATE 4-6-90 4-2-90

Signed Michael R Wilson
(TECHNICIAN)

INV. NO. 27801
3-23