

APR 28 1987

1 070527

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,113-0000

W/2 NW NW, SEC. 29, T 16 S, R 23 W/E

4620 feet from S section line

4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5020

Lease Name Mast Well # 1-29

Operator: Rine Exploration Company

County Ness 148.53

Name & Address 300 West Douglas, Suite 645

Well Total Depth 4570 feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling, Inc. License Number 5422

Address 801 Union Center, Wichita, KS 67202

Company to plug at: Hour: 10:15 a.m. Day: 28 Month: 4 Year: 1987

Plugging proposal received from Wayne Shively

(company name) Abercrombie Drilling, Inc. (phone) 913-743-6308

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2498' GL
Anhydrite 1854-90'

1st plug at 1890' with 50 sx cement, 2nd plug at 960' with 80 sx cement,

3rd plug at 300' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 12:15 p.m. Day: 28 Month: 4 Year: 1987

ACTUAL PLUGGING REPORT 1st plug at 1890' with 50 sx cement,

2nd plug at 1070' with 80 sx cement,

3rd plug at 300' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

(If additional description is necessary, use BACK of this form.)

INVOICED (If additional description is necessary, use BACK of this form.) observe this plugging.

DATE 5-4-87

Signed Dan Gooden (TECHNICIAN) 4-30-87

INV. NO. 16697