

1070787

2-15

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,427-0000

C NW SE, SEC. 25, T 16 S, R 23 W/E

1980 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6009

Lease Name Toedman Well # 1

Operator: Double Eagle Exploration, Inc.
Name &
Address 512 Century Plaza Bldg.
Wichita, KS 67202

County Ness 143.52

Well Total Depth 4416 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 337

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well _____ D&A x

Other well as hereinafter indicated _____

Plugging Contractor Rains & Williamson Oil Company, Inc. License Number 5146

Address 220 West Douglas, Suite 435, Wichita, KS 67202

Company to plug at: Hour: 4 p.m. Day: 15 Month: 2 Year: 1990

Plugging proposal received from Larry Hinderliter

(company name) Rains & Williamson Oil Company, Inc. (phone) 316-265-9686

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1740-59'
Elevation 2388'

1st plug at 1760' with 50 sx cement, 2nd plug at 1000' with 80 sx cement,

3rd plug at 360' with 40 sx cement, 4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn Barlow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Completed: Hour: 6:30 p.m. Day: 15 Month: 2 Year: 1990

ACTUAL PLUGGING REPORT 1st plug at 1760' with 50 sx cement,

2nd plug at 1050' with 80 sx cement,

3rd plug at 340' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1990

2-21-90

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.

(If additional description is necessary, use BACK of this form.)

INVOICED (copy to contractor) observe this plugging.

Signed Dan Gooden
(TECHNICIAN)

DATE 2-23-90

INV. NO. 27551

2-15