

1 020255

10-21

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-23,391-07500  
SW SW SW, SEC. 25, T 16 S, R 23 W/EX  
330 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5815

Lease Name Boyle Well # 1

Operator: C & R Drilling  
Name & Address 410 17th Street, Suite 1140  
Denver, CO 80202

County Ness 142.68  
Well Total Depth 4390 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 335

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Western Kansas Drilling License Number 4083

Address P.O. Box 126, Hays, KS 67601

Company to plug at: Hour: 11 p.m. Day: 20 Month: 10 Year: 19 89

Plugging proposal received from Frang Taggert

(company name) Western Kansas Drilling (phone) 913-628-2296

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2405'  
Anhydrite 1721-53'

- 1st plug at 1750' with 50 sx cement, 2nd plug at 925' with 50 sx cement,
- 3rd plug at 365' with 40 sx cement,
- 4th plug at 40' with 10 sx cement,
- 5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Glenn Barlow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 2:45 a.m. Day: 21 Month: 10 Year: 19 89

- ACTUAL PLUGGING REPORT 1st plug at 1750' with 50 sx cement,
- 2nd plug at 925' with 50 sx cement,
  - 3rd plug at 365' with 40 sx cement,
  - 4th plug at 40' with 10 sx cement,
  - 5th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.  
(If additional description is necessary, use BACK of this form.)

~~Do not~~ observe this plugging.

DATE 10-30-89

Signed Glenn R. Barber  
(TECHNICIAN) *STW*

INV. NO. 26262  
10-21

OCT 24 1989  
10-24-89  
CONSERVATION DIVISION  
WICHITA, KANSAS