

1069186 9-20

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-135-23,776-~~5500~~
150' S & 100' W of
C SW NE, SEC. 24, T 16 S, R 23 W

TECHNICIAN'S PLUGGING REPORT

Operator License # 30336
Operator: Sunflower Exploration
Name: RR 1
Address: Brownell, KS 67521

3150 feet from S section line
2080 feet from E section line

Lease Name Pfaff Well # 1
County Ness
Well Total Depth 4490 145.92 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 218

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A

Other well as hereinafter indicated _____

Plugging Contractor Emphasis Oil Operations License Number 8241

Address P.O. Box 819, Russell, KS 67665-0819

Company to plug at: Hour: 7:15 a.m. Day: 20 Month: 9 Year: 1993

Plugging proposal received from Tom Alm

(company name) Emphasis Oil Operations (phone) 913-483-3518

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1770-1810'
1st plug at 1850' with 50 sx cement, 2nd plug at 850' with 80 sx cement,
3rd plug at 250' with 50 sx cement, 4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 9:30 a.m. Day: 20 Month: 9 Year: 1993

ACTUAL PLUGGING REPORT 1st plug at 1850' with 50 sx cement,
2nd plug at 850' with 80 sx cement,
3rd plug at 250' with 50 sx cement,
4th plug at 40' with 10 sx cement,
5th plug to circulate rathole with 15 sx cement,
6th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-23-93
I (KXXX) did not observe this plugging.

Signed _____ (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
SEP 22 1993
CONSERVATION DIVISION
Wichita, Kansas

INV. NO. 38768