

To: 1 071093
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

9-5

API NUMBER 15-135-22,950

NE NE, SEC. 35, T. 16 S, R. 23 W/R

4620 feet from S section line

660 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6455

Lease Name Klitzke Well # 1

Operator: Apache Drilling Co., Inc.

County Ness 144.62

Name: P.O. Box 454

Address Ness City, KS 67560

Well Total Depth 4450 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 786

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Apache Drilling Co., Inc. License Number 6455

Address P.O. Box 454, Ness City, KS 67560

Company to plug at: Hour: 9:30 a.m. Day: 5 Month: 9 Year: 19 92

Plugging proposal received from Jeff Base

(company name) Apache Drilling Co. (phone) 913-798-3995

were: 5 1/2" at 4450' w/210 sx cement, PBTD 4418', Perfs at 4372-74'

1st plug sand back to 4315' and dump 5 sx cement on top of sand through bailer,

2nd plug cut pipe at 1000', pump 120 sx cement down 5 1/2",

3rd plug pump 30 sx cement down backside.

Plugging Proposal Received by Dan Goodrow
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 10:30 a.m. Day: 5 Month: 9 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4315' and dumped 5 sx cement on top of sand through bailer,

2nd plug cut pipe at 1000', pumped 120 sx cement down 5 1/2", Maximum pressure 900 psi and shut in 0 psi,

3rd plug pumped 30 sx cement down backside, Maximum pressure 500 psi and shut in 0 psi.

NOTE: Less than 4" casing stretch. Well has been cemented up hole but no record exists.

Remarks: Used 60/40 Pozmix 8% gel by Allied. No casing recovery.

If additional description is necessary, use BACK of this form.

I (did / ~~did not~~) observe this plugging.

DATE 9-30-92

36281

Signed Dan Goodrow
(TECHNICIAN)