

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-24200-00-00
Spot: NWNE Sec/Twnshp/Rge: 34-16S-23W
730 feet from N Section Line, 2090 feet from E Section Line
Lease/Unit Name: FERNANN Well Number: 1
County: NESS Total Vertical Depth: 4524 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 210
Production: Size feet:
Liner: Size feet:

Well Type: DH UIC Docket No: Date/Time to Plug: 12/08/2002 11:45 PM
Plug Co. License No.: 4958 Plug Co. Name: MALLARD, J. V., INC.
Proposal Rcvd. from: CAROL Company: MALLARD, J. V., INC. Phone: (620) 241-4640

Proposed Plugging Method: 1ST PLUG AT 1820' WITH 50 SX CMT. 2ND PLUG AT 1100' WITH 80 SX CMT. 3RD PLUG AT 550' WITH 40 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations Were Not Witnessed
Date/Time Plugging Completed: 12/09/2002 1:40 AM KCC Agent: KEVIN STRUBE

Actual Plugging Report:


1ST PLUG AT 1820' WITH 50 SX CMT. 2ND PLUG AT 1100' WITH 80 SX CMT. 3RD PLUG AT 550' WITH 40 SX CMT. 4TH PLUG AT 250' WITH 50 SX CMT. 5TH PLUG AT 40' WITH 10 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 15 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 10 SX CMT.

RECEIVED
DEC 13 2002
12-13-02

Remarks: USED 60/40 POZMIX 6% GEL 1/4# FLO SEAL BY ALLIED.

Plugged through: DP

District: 01



Signed

Kevin D. Strube

(TECHNICIAN)

INVOICED

DATE 12-13-02

NO. 2003060949

Form 2/3