

1 040953 4-16

API NUMBER 15- 135-23,874-0000

STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

NW NE NE, SEC. 33, T 16 S, R 23 W2E
4950 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5003
Operator: McCoy Petroleum Corporation
Name & Address: 3017 N. Cypress
Wichita, KS 67226-4003

Lease Name Schreiber Well # 1-33
County Ness 148.66
Well Total Depth 4574 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 263

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Mallard JV, Inc. License Number 4958

Address P.O. Box 1009, McPherson, KS 67460-1009

Company to plug at: Hour: _____ Day: 16 Month: 4 Year: 1995

Plugging proposal received from Carol
(company name) Mallard JV, Inc. (phone) 316-241-4640

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1815-1855'

1st plug at 1855' with 50.sx cement, 2nd plug at 1000' with 80 sx cement,

3rd plug at 500' with 30 sx cement, 4th plug at 290' with 40 sx cement,

5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Steve Pfeifer (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 1:15 p.m. Day: 16 Month: 4 Year: 1995

ACTUAL PLUGGING REPORT 1st plug at 1855' with 50 sx cement,

2nd plug at 1000' with 80 sx cement,

3rd plug at 500' with 30 sx cement,

4th plug at 290' with 40 sx cement, 5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement,

7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

Observe this plugging.

INVOICED

DATE 4-26-95

INV. NO. 42696

Signed Stephen J. Pfeifer (TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
4-20-95
APR 20 1995
CONSERVATION DIVISION
WICHITA, KANSAS