

To: 1 070640  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION App.  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-135-23,314-0000  
N/2 SW SE, SEC. 33, T 16 S, R 23 W/EX  
1250 feet from S section line  
1900 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 7185  
Operator: Luff Exploration Company  
Name & Address: 1580 Lincoln St., Suite 850  
Denver, CO 80203

Lease Name Sargent Well # 0-30  
County Ness 147.81  
Well Total Depth 4548 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 311

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Duke Drilling Company, Inc. License Number 5929  
Address 205 East Central, Suite 120, Wichita, KS 67202

Company to plug at: Hour: 10 a.m. Day: 1 Month: 2 Year: 19 89

Plugging proposal received from Pete Musgrove

(company name) Duke Drilling Company, Inc. (phone) 316-267-1331

were: to fill hole with heavy mud and spot cement through drill pipe Elevation 2466'  
Anhydrite 1804-39'

1st plug at 1790' with 50 sx cement, 2nd plug at 900' with 80 sx cement,  
3rd plug at 340' with 40 sx cement, 4th plug at 40' with 10 sx cement,  
5th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part  None \_\_\_\_\_

Operations Completed: Hour: 12:45 p.m. Day: 1 Month: 2 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug at 1790' with 50 sx cement,

2nd plug at 900' with 80 sx cement,

3rd plug at 340' with 40 sx cement,

4th plug at 40' with 10 sx cement,

5th plug to circulate rathole with 15 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
2-6-89  
FEB 6 1989  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 2-8-89

Signed Dan Jordan (TECHNICIAN)

INV. NO. 23889