

To: 1 060023 3-11
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202
TECHNICIAN'S PLUGGING REPORT

API NUMBER 15-135-23,979-0060
NE SE NW, SEC. 32, T 16 S, R 23 W XX
3630 feet from S section line
2970 feet from E section line

Operator License # 5011
Operator: Viking Resources, Inc.
Name & Address: 105 S. Broadway, Ste. 1040
Wichita, KS. 67202

Lease Name Keith Well # 1
County Ness 148.85
Well Total Depth 4580 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 232

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SMD Well _____ O&A X
Other well as hereinafter indicated _____

Plugging Contractor Mallard JV, Inc. License Number 4958
Address P.O. Box 1009, McPherson, KS 67460-1009

Company to plug at: Hour: 11 a.m. Day: 11 Month: 3 Year: 19 97
Plugging proposal received from Arnie Hess
(company name) Mallard JV, Inc. (phone) 316-241-4640

were: to fill hole with heavy mud and spot cement through drill pipe Base Anhydrite 1857'
1st plug at 1857' with 50 sx cement, 2nd plug at 1000' with 50 sx cement,
3rd plug at 650' with 50 sx cement, 4th plug at 260' with 50 sx cement,
5th plug at 40' with 10 sx cement, 6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Mike Maier (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____
Operations Completed: Hour: 2 p.m. Day: 11 Month: 3 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 1857' with 50 sx cement,
2nd plug at 1000' with 50 sx cement, 3rd plug at 650' with 50 sx cement,
4th plug at 260' with 50 sx cement, 5th plug at 40' with 10 sx cement,
6th plug to circulate rathole with 15 sx cement,
7th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
I hereby agree to reserve this plugging.

DATE MAR 18 1997
INV. NO. 47771

Signed Michael J. Maier (TECHNICIAN)

RECEIVED
MANSAS CORP
CC/M
3-18-97
1997 MAR 18 12:52

3-11