

To: 1 030549  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION NW SE SW  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,937-0006  
\_\_\_\_\_ feet from S section line  
990  
\_\_\_\_\_ feet from E section line  
3630

TECHNICIAN'S PLUGGING REPORT

Operator License # 5161  
Operator: Palomino Petroleum  
Name & Address P. O. Box 18610  
Wichita, KS 67218

Lease Name Mishler "M" Well # 2  
County Ness 147.88  
Well Total Depth 4550 Mississippi feet ✓  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 250

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor DNB Drilling, Inc. License Number 5476  
Address 535 North Oliver, Wichita, KS 67208

Company to plug at: Hour: 7:00 pm Day: 10 Month: October Year: 19 85

Plugging proposal received from Jack Taylor

(company name) DNB (phone) 316-687-5471  
Elevation 2448 GL

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1787-1820'

- 1st plug at the base of the Anhydrite with 50 sx cement
- 2nd plug 50' below the base of the Cheyenne with 80 sx cement
- 3rd plug 30' below the base of the surface pipe with 40 sx cement  
solid bridge
- 4th plug hulls - plug at 40' -- cement to surface with 10 sx cement
- 6th plug to circulate rat hole with 10 sx cement

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 9:15 pm Day: 10 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1820' with 50 sx cement, 2nd plug at 760' with 80 sx  
cement, 3rd plug at 280' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls -  
plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole  
with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION

10-15-85  
OCT 15 1985

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary use back of this form.)

CONSERVATION DIVISION  
Wichita, Kansas  
Signed Steve Durrant  
(TECHNICIAN)

INVOICED  
DATE OCT 17 1985  
INV. NO. 10661