

To: 1 110010
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 135-22,918 -0000

SE SW SW, SEC. 32, T 16 S, R 23 (W) E

330 feet from S section line

4290 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5161

Lease Name Mishler "L" Well # 2

Operator: Palomino Petroleum
Name & Address: P. O. Box 18610
Wichita, KS 67218

County Ness 148.53

Well Total Depth 4570 Mississippi feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 249

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor DNB Drilling, Inc. License Number 5476

Address 535 North Oliver, Wichita, KS 67208

Company to plug at: Hour: 1:00 pm Day: 2 Month: October Year: 19 85

Plugging proposal received from John Taylor

(company name) DNB (phone) 316-687-5471
elevation 2485

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1855-80'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug at the base of the Cheyenne with 80 sx cement

3rd plug at 500' with 40 sx cement

4th plug 30' out of the base of the surface pipe with 40 sx cement
solid bridge - hulls - plug at 40'

5th plug cement to surface Plugging Proposal Received by James R. Kapp
with 10 sx cement (TECHNICIAN)

7th plug to circulate rat hole with 10 sx cement
Plugging Operations attended by Agent: All Part None X

Operations Completed: Hour: 3:30 pm Day: 2 Month: October Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 1855' with 50 sx cement, 2nd plug at 950' with 80 sx
cement, 3rd plug at 500' with 40 sx cement, 4th plug at 250' with 40 sx cement, 5th & 6th

plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 7th

plug to circulate rat hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.
(If additional description is necessary, use BACK of this form.)

INVOICED
DATE 10-15-85
REV. NO. 10573
10-2

RECEIVED
OCT 11 1985
10-4-85
CONSERVATION DIVISION

Signed James R. Kapp
(TECHNICIAN)